

Wayne County Juvenile Center

Date: 2019

Location: Detroit, MI

Advantage: Saves Time
& Storage Space



Barton Malow Co.
Southfield, MI
www.bartonmalow.com



Technical Specifications

Application: Slab-on-Metal Deck

Fiber Reinforcement: FORTA-FERRO[®] 2-1/4"

Fibers Specified: Replaced Single Layer
WWF 6x6 – W4.0xW4.0

Dosage: 5.0 lb/cu yd

Delivery Method: Pumped

Finishing Method: Steel-Troweled



This newly constructed multi-story building used **FORTA-FERRO** macro synthetic fibers in lieu of welded wire fabric. This eliminated the space needed to store and the time need to place WWF. The Preferred Contractor, Barton Malow, uses FORTA's most popular fiber reinforcement **in all project possible**.

World-class design services, on-site support. *Contact us to learn more.*