

Polk St. Apartments

Date: 2022

Location:
Robinson Township, PA

Advantage:
Cost Savings



Bazzella Group
Whitehall, PA
www.bazellagroup.com



Technical Specifications

Fiber Reinforcement: FORTA-FERRO[®] 2 1/4"

Application: Slab-on-Ground

Doasge: 3.0 lb/cu yd

Total Project Size: 600 yds

Replaced: 6x6 w1.4 Specified Steel

Finishing Method: Steel-Troweled



Contractors replaced specified steel reinforcement with **FORTA-FERRO** macro synthetic fibers in this newly constructed apartment complex. The use of fiber reinforcement is a **lower cost** alternative to buying and placing traditional steel methods. This **saved** both owners and the contractor **time and money**.

World-class design services, on-site support. *Contact us to learn more.*