


# Wyatt, Inc.

**Date:** 2023

**Location:** Smithton, PA

**Advantage:** Cost Savings



## Technical Specifications

**Fiber Reinforcement:** FORTA-FERRO<sup>®</sup> 2-1/4"

**Application:** Slab-on-Ground

**Dosage:** 3.0 lb/cu yd

**Total Project Size:** 200,000 sq ft

**Replaced:** Specified 6x6 Wire Mesh

**Delivery Method:** Pumped & Tailgated

**Finishing Method:** Steel-Troweled



The use of **FORTA-FERRO** reinforcement fibers allowed for faster placement of the concrete and will give owners a **better wearing surface** on the slab. Even though this project was completed in a Northeast winter climate, the mixing & finishing capabilities of this macro synthetic fiber grant **increased ease of use and placement**.

**World-class design services, on-site support. *Contact us to learn more.***